



COMMISSIONERS

Blaine R. Young
President
C. Paul Smith
Vice President

Billy Shreve

David P. Gray

Kirby Delauter

COUNTY MANAGER

David B. Dunn


FINANCE DIVISION

Lori L. Depies, CPA
Director

PROCUREMENT AND CONTRACTING DEPARTMENT

Harold E. (Hal) Good, CPPO
Director

Bruce R. Johnson, CPPO
Manager



CHARACTER COUNTS! and the Six Pillars of Character are service marks of the CHARACTER COUNTS! Coalition, a project of the Josephson Institute of Ethics.
www.charactercounts.org

FINANCE DIVISION FREDERICK COUNTY, MARYLAND

Department of Purchasing

Winchester Hall • 12 East Church Street • Frederick, Maryland 21701
(301) 600-1069 • FAX (301) 600-2521 • TTY Use Maryland Relay
www.FrederickCountyMD.gov

May 14, 2012

Bid No. 12-CP-15

New Design Road Transmission Main Effluent Backflow Preventer
Frederick County
Contract No. 110A8-W

Addendum No. 3

This addendum contains revisions, clarifications, and information pertinent to the bid documents of the referenced project and shall supplement, amend, and become part of the procurement documents for the title project and contract. All bids shall be based on this Addendum, in accordance with the bid documents.

This Addendum consists of 2 sheets including clarifications in response to questions. Acknowledgment of this addendum shall be made on the Proposal Form, including addendum number and date. Failure to acknowledge addendum may subject the bidder to disqualification.

Bids will be received until 3:00 PM local time, May 17, 2012.

Except as noted herein, all terms and conditions of the document referenced, as heretofore changed, remain unchanged and in full force and effect.


Tim Kepp, Procurement Manager

CLARIFICATIONS

1. **ADD** the following clarification:

Question: In Addendum No. 2, Clarification Number 4, Response, the answer states "SPS #1 where the backflow preventer shall be placed is abandoned." From drawing BFP-1, it shows the BFP in Ex. Pumping Station #1. Please clarify that the Backflow Preventer will be installed in the Ex. Pumping Station #1 and not SPS #1.

Response: Per Drawing BFP-1, the backflow preventer will be built in "Existing Pumping Station #1".

2. **ADD** the following clarification:

Question: In Addendum No. 2, Clarification Number 4, Response, the answer states that "There is no need for a bypass". Has the flow into this station already been plugged?

Response: The existing 8" influent sewer to Existing Pumping Station #1 was abandoned as part of Contract 147B-S.

3. **ADD** the following clarification:

Question: In regards to the borings, it seems that the soil has very low blow counts. Will the contractor be required to haul this material offsite and replace it with new material? Or can the soil be stored on site and reused as backfill in the pipe trench?

Response: On-site material may be used for backfill as long as it meets the County earthwork standards as defined in County Standard Specification Section 02200.